BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work: Improvements to Roads and Drains at Badrappa Layout and Surrounding area in Ward No. 08, Kodigehalli.

Sl. No.	Quantity.	Description	Unit	Sri Sambashiva Reddy. C	
				In Figures	In Words
1	346.50	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, **in hard soil** not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods etc.,complete as per specification and direction of engineer in charge	Cum	78.87	Rupees Seventy Eight and Eighty Seven Paise Only
2	57.75	Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation**, including cost of all materials, labour, HOM of machinery, curing etc.,complete as per specification and direction of engineer in charge	Cum	4681.81	Rupees Four Thousand Six Hundred Eighty One and Eighty One Paise Only
3	136.50	Providing and laying in position **reinforced cement concrete of Design mix M20** with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works **in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc.,** including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement etc.,complete as per specification and direction of engineer in charge	Cum	5890.58	Rupees Five Thousand Eight Hundred Ninety and Fifty Eight Paise Only
4	8.19	Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - **TMT bars Fe 500** etc.,complete as per specification and direction of engineer in charge	Tonne	58300.90	Rupees Fifty Eight Thousand Three Hundred and Ninety Paise Only
5	1050.00	Providing and removing **centering, shuttering, strutting, propping** etc., and removal of form work for **vertical surface such as walls at any thickness**, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour etc.,complete as per specification and direction of engineer in charge	Sqm	281.85	Rupees Two Hundred Eighty One and Eighty Five Paise Only
6	135.00	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing etc.,complete as per specification and direction of engineer in charge	Sqm	749.35	Rupees Seven Hundred Forty Nine and Thirty Five Paise Only

C. Samba Shiva Reddy
Signature of the Contractor

14/01
Executive Engineer

14/01

Sl. No.	Quantity.	Description	Unit	Sri Sambashiva Reddy. C	
				In Figures	In Words
7	750.00	Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded) etc.,complete as per specification and direction of engineer in charge	m	33.66	Rupees Thirty Three and Sixty Six Paise Only
8	778	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete as per specification and direction of engineer in charge	No	301.09	Rupees Three Hundred One and Nine Paise Only
9	157.50	Providing and applying ready mix priming coat **over concrete** / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc.,complete as per specification and direction of engineer in charge	Sqm	25.01	Rupees Twenty Five and One Paise Only
10	157.50	Providing and applying floor painting with ready mix paint in two coats (exluding priming coat) on new concrete / asbestos cement sheet / plastered surfaces brushing to give an even shade after preparing the surface after throughly cleaning oil, dirt, dust other foreign matter and sand papering including cost of materials, labour, etc.,complete as per specification and direction of engineer in charge	Sqm	48.09	Rupees Forty Eight and Nine Paise Only
11	346.50	Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip etc.,complete as per specification and direction of engineer in charge	cum	96.19	Rupees Ninety Six and Nineteen Paise Only
		EIRL			
E1	183.60	Providing **precast slab of 100mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per specification and direction of engineer in charge	Sqm	2120.83	Rupees Two Thousand One Hundred Twenty and Eighty Three Paise Only

C Sambha Shiva Reddy
Signature of the Contractor

14/01
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

14/01